					ST DEPARTMENT DIVISION C		URAL RESC		3		AMENI	FC DED REPOR	RM 3	
		AF	PPLICATION FO	OR PERM	IT TO DRILL					1. WELL NAME and N	UMBER NBU 921	-24A1BS		
2. TYPE O	F WORK	DRILL NEW WELL	REENTER	P&A WELL	3. FIELD OR WILDCAT NATURAL BUTTES									
4. TYPE O	F WELL				hane Well: NO	5. UNIT OF COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES						1E		
6. NAME (OF OPERATOR		KERR-MCGEE OIL		7.0					7. OPERATOR PHONE				
8. ADDRE	SS OF OPERAT									9. OPERATOR E-MAII	L			
	AL LEASE NUM		P.O. Box 173779		NERAL OWNERS	SHIP				12. SURFACE OWNER		anadarko	.com	
		JTU 0149076		FED	ERAL (III) IND	DIAN 🔵	STATE () FEE		-	DIAN 🔳			EE 💮
13. NAME	OF SURFACE	OWNER (if box 12	= 'fee')							14. SURFACE OWNER	R PHONE	(if box 12	= 'fee')	
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 16. SURFACE OWNER E-MAIL (if box 12 = 'fee')											! = 'fee')			
17. INDIAN ALLOTTEE OR TRIBE NAME (If box 12 = 'INDIAN') 18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS 19. SLANT														
Ute Indian Tribe YES (Submit Commingling Application) NO VERTICAL DIRECTIONAL HORIZONTAL											TAL 🔵			
20. LOCATION OF WELL FOOTAGES QTR-QTR SECTION TOWNSHIP RANGE MERIDIAN												RIDIAN		
LOCATION AT SURFACE 239 FNL 445 FEL NENE 24 9.0 S 21.0 E S												S		
Top of U	ppermost Prod	lucing Zone	83		24	9.0 S	2	1.0 E		S				
At Total	Depth		83	FNL 505	FEL	NE	ENE		24	9.0 S	2	1.0 E		S
21. COUN	TY	UINTAH		22. DIS	22. DISTANCE TO NEAREST LEASE LINE (Feet) 83					23. NUMBER OF ACR	ES IN DR		IT	
					STANCE TO NEA ied For Drilling		leted)	POOL		26. PROPOSED DEPT		TVD: 109	148	
27. ELEV	ATION - GROUN	ID LEVEL		28. BC	OND NUMBER	032				29. SOURCE OF DRIL				
		4898				WYB00	00291		WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-8496					LE
01.11		0		147 . 1 . 1 . 4	Hole, Casing	•			n	2				144.1.1.4
String Surf	Hole Size	Casing Size 8.625	0 - 2950	Weight 28.0	Grade & T		Max Mu		-	Cement Type V		Sacks 180	Yield 1.15	Weight 15.8
- Cuii		0.020	0 2000	20.0	0 00 2		- ·			Class G		270	1.15	15.8
Prod	7.875	4.5	0 - 10952	11.6	HCP-110	LT&C	12	.5	Pre	mium Lite High Stre	ength	350	3.38	12.0
										50/50 Poz		1530	1.31	14.3
					А	TTACHN	MENTS							
	VER	RIFY THE FOLLO	WING ARE AT	TACHED I	IN ACCORDAN	ICE WITH	H THE UTA	AH OIL A	AND GAS	CONSERVATION G	SENERA	L RULES		
₩ w	ELL PLAT OR M	AP PREPARED BY	LICENSED SURVE	YOR OR E	NGINEER		СОМ	PLETE D	RILLING P	LAN				
AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER														
I ✓ DII	DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) TOPOGRAPHICAL MAP													
NAME La	ura Abrams			TITLE R	egulatory Analyst	t II			PHONE 7	720 929-6356				
SIGNATU	IGNATURE DATE 05/29/2012 EMAIL Laura.Abrams@anadarko.com													
	BER ASSIGNED)47527680			APPROV	'AL				Perm	OGGILL it Manager				
I				I										

NBU 921-24A Pad Drilling Program

1 of 4

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 921-24A1BS

Surface: 239 FNL / 445 FEL NENE BHL: 83 FNL / 505 FEL NENE

Section 24 T9S R21E

Unitah County, Utah Mineral Lease: UTU-0149076

ONSHORE ORDER NO. 1

DRILLING PROGRAM

8 2.a <u>Estimated Tops of Important Geologic Markers</u>: Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,658'	
Birds Nest	1,928'	Water
Mahogany	2,496'	Water
Wasatch	4,958'	Gas
Mesaverde	7,663'	Gas
Sego	9,858'	Gas
Castlegate	9,932'	Gas
Blackhawk	10,348'	Gas
TVD =	10,948'	
TD =	10,952'	

2.c Kerr McGee Oil & Gas Onshore LP (Kerr McGee) may elect to drill to (i) the Blackhawk formation (part of the Mesaverde Group), (ii) to a shallower depth within the Mesaverde Group, or (iii) to the Wasatch Formation. If Kerr McGee drills to Blackhawk formation, please refer to Blackhawk as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr-McGee drills to a shallower depth in the Mesaverde Group or to the Wasatch Formation, please refer to the attached Wasatch/Mesaverde Drilling Program which includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the shallower formations.

3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

5. <u>Drilling Fluids Program:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

NBU 921-24A Pad Drilling Program 2 of 4

6. Evaluation Program:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

7. <u>Abnormal Conditions</u>:

7.a Blackhawk (Part of Mesaverde Group)

Maximum anticipated bottom hole pressure calculated at 7,007 psi (0.64 psi/ft = actual bottomhole gradient) approximately equals

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,583 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

7.b Wasach Formation/Mesaverde Group

Maximum anticipated bottom hole pressure calculated at 9858' TVD, approximately equals 6,013 psi (0.61 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,871 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. <u>Variances:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- · Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

NBU 921-24A Pad Drilling Program

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

3 of 4

NBU 921-24A Pad Drilling Program
4 of 4

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. Other Information:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program



KERR-McGEE OIL & GAS ONSHORE LP Blackhawk Drilling Program

COMPANY NAME KER	R-McGEE OIL 8	GAS ONSHORI	E LP		DATE	March 28,	2012		
WELL NAME NB	J 921-24A1B	S			TD	10,948'	TVD	10,952' MD	
FIELD Natural Butte	S	COUNTY	Uintah S	STATE Uta	h	FINIS	HED ELEVATION	4,898'	
SURFACE LOCATION	NENE	239 FNL	445 FEL	Sec 24	T 9S	R 21E			
	Latitude:	40.028078	Longitude	: -109.49	2284		NAD 83		
BTM HOLE LOCATION	NENE	83 FNL	505 FEL	Sec 24	T 9S	R 21E			
	Latitude:	40.028505	Longitude	: -109.49	2498		NAD 83		
OBJECTIVE ZONE(S)	BLACKHAWK	(Part of the Mesa	averde Group)				_		
ADDITIONAL INFO	Regulatory Ag	encies: BLM (Min	erals), Ute Indi	ian Tribe (Sι	urface), U	IDOGM Tri-Co	unty Health Dept.		





KERR-McGEE OIL & GAS ONSHORE LP Blackhawk Drilling Program

CASING PROGRAI	<u>VI</u>								DESIGN F.	ACTORS	
										LTC	DQX
	SIZE	INT	ERVA	L	WT.	GR.	CPLG.	BURST	COLLAPSE	TE	NSION
CONDUCTOR	14"	(0-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,950	28.00	IJ-55	LTC	1.82	1.36	4.81	N/A
								10,690	8,650	279,000	367,174
PRODUCTION	4-1/2"	0	to	5,000	11.60	HCP-110	DQX	1.19	1.22		3.57
	4-1/2"	5,000	to	10,952'	11.60	HCP-110	LTC	1.19	1.22	5.00	

Surface Casing:

(Burst Assumptions: TD =

12.5 ppg)

0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above (Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @

9000 psi)

0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	Г	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1		+ 0.25 pps flocele					
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
		+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water to	o surface, op	tion 2 will be	e utilized		
Option 2 LEAD	2,450'	65/35 Poz + 6% Gel + 10 pps gilsonite	230	35%	11.00		3.82
		+ 0.25 pps Flocele + 3% salt BWOW					
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
		+ 0.25 pps flocele					
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION LEAD	4,452'	Premium Lite II +0.25 pps	350	35%	12.00		3.38
		celloflake + 5 pps gilsonite + 10% gel					
		+ 0.5% extender					
TAIL	6,500'	50/50 Poz/G + 10% salt + 2% gel	1,530	35%	14.30		1.31
		+ 0.1% R-3					

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys	will be	taken at	1,000'	minimum	intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER:		DATE:	
	Nick Spence / Danny Showers / Chad Loesel	•	
DRILLING SUPERINTENDENT:		DATE:	
	Kenny Gathings / Lovel Young	•	

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained



KERR-McGEE OIL & GAS ONSHORE LP Wasatch/Mesaverde Drilling Program

COMPANY NAME KER	R-McGEE OIL 8	GAS ONSHOR	E LP		DATE	March 28,	2012	
WELL NAME NB	U 921-24A1E	SS			TD	9,858'	TVD	9,862' MD
FIELD Natural Butte	S	COUNTY	Uintah	STATE Uta	h	FINI	SHED ELEVATION	4,898'
SURFACE LOCATION	NENE	239 FNL	445 FEL	Sec 24	T 9S	R 21E		
	Latitude:	40.028078	Longitude	: -109.49	2284		NAD 83	
BTM HOLE LOCATION	NENE	83 FNL	505 FEL	Sec 24	T 9S	R 21E		
	Latitude:	40.028505	Longitude	: -109.49	2498		NAD 83	
OBJECTIVE ZONE(S)	Wasatch Form	nation/Mesaverde	e Group					
ADDITIONAL INFO	Regulatory Ag	encies: BLM (Mi	nerals), Ute Inc	dian Tribe (Si	urface), L	JDOGM Tri-Co	ounty Health Dept.	





KERR-McGEE OIL & GAS ONSHORE LP
Wasatch/Mesaverde Drilling Program

CASING PROGRAM	<u>1</u>								DESIGN F	ACTORS	
										LTC	DQX
	SIZE	INT	ERVA	L	WT.	GR.	CPLG.	BURST	COLLAPSE	TE	NSION
CONDUCTOR	14"	()-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,950	28.00	IJ-55	LTC	1.82	1.36	4.81	N/A
								7,780	6,350		267,035
PRODUCTION	4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.03		2.86
								7,780	6,350	223,000	
	4-1/2"	5,000	to	9,862'	11.60	I-80	LTC	1.11	1.03	4.84	

Surface Casing:

(Burst Assumptions: TD = 12.0 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.61 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

1	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGH	Т	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15
Option 1		+ 0.25 pps flocele					
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15
		+ 2% CaCl + 0.25 pps flocele					
SURFACE		NOTE: If well will circulate water to	surface, opt	ion 2 will be	utilized		
Option 2 LEAD	2,450'	65/35 Poz + 6% Gel + 10 pps gilsonite	230	35%	11.00		3.82
		+ 0.25 pps Flocele + 3% salt BWOW					
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15
		+ 0.25 pps flocele					
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15
PRODUCTION LEAD	4,452'	Premium Lite II +0.25 pps	350	35%	12.00		3.38
		celloflake + 5 pps gilsonite + 10% gel					
		+ 0.5% extender					
TAIL	5,410'	50/50 Poz/G + 10% salt + 2% gel	1,280	35%	14.30		1.31
		+ 0.1% R-3					

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

	Surveys will be taken at 1,000' minimum intervals.	
	Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.	·
DRILLING	ENGINEER:	DATE:

Nick Spence / Danny Showers / Chad Loesel

DRILLING SUPERINTENDENT:


Kenny Gathings / Lovel Young

Nick Spence / Danny Showers / Chad Loesel


DATE:

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained


EXHIBIT A NBU 921-24A1BS




SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



		CIII	DEACE DOCUTIO	NI .			n	OTTOM HOLE		
WELL NAME	NAE		RFACE POSITIO NAC			NA	D83	OTTOM HOLE NAE	D27	
	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	FOOTAGES
NBU 921-24A4CS	40°01'41.051" 40.028070°	109°29'31.838" 109.492177°	40°01'41.177" 40.028105°	109°29'29.367" 109.491491°	242' FNL 415' FEL	40°01'32.837' 40.025788°	109°29'32.899" 109.492472°	40°01'32.963" 40.025823°	109°29'30.428" 109.491785°	1073' FNL 498' FEL
NBU	40°01'41.060"	109°29'31.966"	40°01'41.187"	109°29'29.495"	241' FNL	40°01'36.097'	109°29'32.913"	40°01'36.224"	109°29'30.442"	743' FNL
921-24A4BS NBU	40.028072° 40°01'41.071"	109.492213° 109°29'32.094"	40.028107° 40°01'41.198"	109.491526° 109°29'29.622"	425' FEL 240' FNL	40.026694° 40°01'39.357'	109.492476° 109°29'32.915"	40.026729° 40°01'39.484"	109.491789° 109°29'30.443"	499' FEL 413' FNL
921-24A1CS	40.028075°	109.492248°	40.028110°	109.491562°	435' FEL	40.027599°	109.492476°	40.027634°	109.491790°	499' FEL
NBU 921-24A1BS	40°01'41.080" 40.028078°	109°29'32.221" 109.492284°	40°01'41.207" 40.028113°	109°29'29.750" 109.491597°	239' FNL 445' FEL	40°01'42.618' 40.028505°	109°29'32.994" 109.492498°	40°01'42.744" 40.028540°	109°29'30.522" 109.491812°	83' FNL 505' FEL
			RELATIVE (COORDINATES	- From Surface	Position to Bot			I.	
WELL NAME	NORTH			ORTH EAS		NAME NOI		WELL NAM	IE NORTH	EAST
NBU 921-24A4CS	-831.3'	-82.8 NBU 921	-24A4BS -5	02.3' -73.	8 NBU 921-24	A1CS -17.	3.4' -63.9'	NBU 921-24A1B	s 155.7'	-60.1'
		Bottom Hole	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	\	NBU 921-24A1BS O 1 NBU 921-24A1CS O 1 NBU 921-24A4BS NBU 921-24A4CS	- 	<u>S8</u>	50 50 4°22'47"E 95.62028°	N To CALE	,09
THE S.L.B GLOI	NE ¼ OF SECTI .&M. WHICH BAL POSITION	GS IS THE EAST ION 24, T9S, R IS TAKEN FRO NING SATELLIT O BEAR NO0°C Botto Hole	21E, M E 10'11"W. / m of —— •	AZ=188.36222	041'11"W - 835.46'	$AZ=185.68639^{\circ}$		3.02028		
WELL WELLS - N	Bth Street - Del L PAD - N . PAD INTE	A Gas Ons nver, Colorado NBU 921-2 RFERENCE 4CS, NBU 921	80202 24A PLAT -24A4BS,		609 ULTING, LLO	C DAT	IMBERL ENGINEERIN 209 NORTH: TE SURVEYED: 31-11		SURVEYINC NAL, UTAH 84	*
		R NBU 921-24			orth Main Stre an WY 82801	et DA1	TE DRAWN:	DRAWN BY:	J.G.C.	5
		ION 24, T9S, I I COUNTY, U		Phone	307-674-060	9 09-0	09-11 SCALE: 1" = 60'	Date Last Rev		J
	•	,		Fax 3	307-674-0182					5 OF 16








PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: SOUTHERLY

Kerr-McGee Oil & Gas Onshore, LP

WELL PAD - NBU 921-24A

LOCATION PHOTOS
NBU 921-24A4CS, NBU 921-24A4BS,
NBU 921-24A1CS & NBU 921-24A1BS
LOCATED IN SECTION 24, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC 2155 North Main Street Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182

T	I	٨	1	В	E	R	L	I	1	1	E	
	С	N		IN	I C	ED	IN	10	_	Q	. 1	


(435) 789-1365


ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


08-31-11	PHOTOS TAKEN BY: J.W.
DATE DRAWN: 09-09-11	DRAWN BY: J.G.C
Date Last Revised:	


9 OF 16


SHEET NO:














Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 921-24A WELLS - NBU 921-24A4CS, NBU 921-24A4BS, NBU 921-24A1CS & NBU 921-24A1BS Section 24, T9S, R21E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East street in Vernal, Utah, proceed in an easterly, then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 16.1 miles to a service road to the northwest. Exit right and proceed in a northwesterly direction along the service road approximately 0.3 miles to a second service road to the west. Exit left and proceed in a westerly direction along the second service road approximately 0.2 miles to a third service road and through the existing NBU 921-13P well pad approximately 0.2 miles to the proposed access road to the south. Follow road flags in a southerly, then southeasterly direction approximately 820 feet to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 40.5 miles in a southerly direction.

SHEET 16 OF 16


API Well Number: 43047 520 Jec 8 00 TAB - UTM (feet), NAD27, Zone 12N


Site: NBU 921-24A PAD Well: NBU 921-24A1BS


Wellbore: OH

Design: PLAN #1 PRELIMINARY









CASTLEGATE

BLACKHAWK

750

TD at 10952.29

Vertical Section at 338.84° (1500 ft/in)

1500

BLACKHAWK_NBU 921-24A1BS

2250

3000

9000

9750

10500

11250

-750


SEGO


10948.00

0

Scientific Drilling

Rocky Mountain Operations





RECE:

Plan: PLAN #1 PRELIMINARY (NBU 921-24A1BS/OH)

Date: 10:38. November 21 2011

Created By: RobertScott



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N NBU 921-24A PAD NBU 921-24A1BS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

21 November, 2011





SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-24A PAD

 Well:
 NBU 921-24A1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-24A1BS

GL 4898 & KB 4 @ 4902.00ft (ASSUMED) GL 4898 & KB 4 @ 4902.00ft (ASSUMED)

True

Minimum Curvature

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System: Universal Transverse Mercator (US Survey Feet)

 Geo Datum:
 NAD 1927 (NADCON CONUS)

 Map Zone:
 Zone 12N (114 W to 108 W)

Mean Sea Level

Site NBU 921-24A PAD, SECTION 24 T9S R21E

Northing: 14,539,855.88 usft Site Position: Latitude: 40° 1' 41.196 N From: Lat/Long Easting: 2,062,702.51 usft Longitude: 109° 29' 29.623 W **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 0.97 13.200 in

System Datum:

ostion oncertainty.

Well NBU 921-24A1BS, 239 FNL 445 FEL

 Well Position
 +N/-S
 1.09 ft
 Northing:
 14,539,856.81 usft
 Latitude:
 40° 1' 41.207 N

 +E/-W
 -9.80 ft
 Easting:
 2,062,692.70 usft
 Longitude:
 109° 29' 29.749 W

Position Uncertainty 0.00 ft Wellhead Elevation: Ground Level: 4,898.00 ft

Wellbore ОН Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (nT) (°) (°) IGRF2010 2011/11/21 11.02 65.88 52.303

PLAN #1 PRELIMINARY Design Audit Notes: Version: Phase: PLAN Tie On Depth: 0.00 Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 338.84

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
450.00	3.00	338.84	449.93	3.66	-1.42	2.00	2.00	0.00	338.84	
3,475.64	3.00	338.84	3,471.43	151.33	-58.58	0.00	0.00	0.00	0.00	
3,647.07	0.00	0.00	3,642.78	155.52	-60.20	1.75	-1.75	0.00	180.00	
10,952.29	0.00	0.00	10,948.00	155.52	-60.20	0.00	0.00	0.00	0.00 F	BHL_NBU 921-24A



SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-24A PAD

 Well:
 NBU 921-24A1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-24A1BS

GL 4898 & KB 4 @ 4902.00ft (ASSUMED) GL 4898 & KB 4 @ 4902.00ft (ASSUMED)

True

Minimum Curvature

	FLAN#IFRE								
d Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2.00	0.00	0.00	2.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2									
152.00	0.00	0.00	152.00	0.00	0.00	0.00	0.00	0.00	0.00
	4 hold at 152.00								
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	2.00	338.84	399.98	1.63	-0.63	1.75	2.00	2.00	0.00
450.00	3.00	338.84	449.93	3.66	-1.42	3.93	2.00	2.00	0.00
500.00	3.00	338.84	499.86	6.10	-2.36	6.54	0.00	0.00	0.00
600.00 700.00	3.00 3.00	338.84 338.84	599.73 699.59	10.98 15.86	-4.25 -6.14	11.78 17.01	0.00 0.00	0.00 0.00	0.00 0.00
800.00	3.00	338.84	799.45	20.74	-8.03	22.24	0.00	0.00	0.00
900.00 1,000.00	3.00 3.00	338.84 338.84	899.31 999.18	25.62 30.51	-9.92 -11.81	27.48 32.71	0.00 0.00	0.00 0.00	0.00 0.00
1,100.00	3.00	338.84	1,099.04	35.39	-11.61	37.94	0.00	0.00	0.00
1,200.00	3.00	338.84	1,198.90	40.27	-15.59	43.18	0.00	0.00	0.00
1,300.00	3.00	338.84	1,298.77	45.15	-17.48	48.41	0.00	0.00	0.00
1,400.00	3.00	338.84	1,398.63	50.03	-19.37	53.65	0.00	0.00	0.00
1,500.00	3.00	338.84	1,498.49	54.91	-21.25	58.88	0.00	0.00	0.00
1,600.00	3.00	338.84	1,598.36	59.79	-23.14	64.11	0.00	0.00	0.00
1,659.73	3.00	338.84	1,658.00	62.70	-24.27	67.24	0.00	0.00	0.00
GREEN RIV									
1,700.00	3.00	338.84	1,698.22	64.67	-25.03	69.35	0.00	0.00	0.00
1,800.00	3.00	338.84	1,798.08	69.55	-26.92	74.58	0.00	0.00	0.00
1,900.00	3.00	338.84	1,897.94	74.43	-28.81	79.81	0.00	0.00	0.00
1,930.10	3.00	338.84	1,928.00	75.90	-29.38	81.39	0.00	0.00	0.00
BIRDSNEST		000.04	4 007 04	70.04	00.70	05.05	0.00	0.00	0.00
2,000.00 2,100.00	3.00 3.00	338.84 338.84	1,997.81 2,097.67	79.31 84.19	-30.70 -32.59	85.05 90.28	0.00 0.00	0.00 0.00	0.00 0.00
2,200.00	3.00	338.84 338.84	2,197.53	89.07 93.95	-34.48 -36.37	95.51 100.75	0.00 0.00	0.00 0.00	0.00
2,300.00 2,400.00	3.00 3.00	338.84	2,297.40 2,397.26	98.83	-36.37 -38.26	100.75	0.00	0.00	0.00 0.00
2,498.88	3.00	338.84	2,496.00	103.66	-40.13	111.16	0.00	0.00	0.00
MAHOGAN									
2,500.00	3.00	338.84	2,497.12	103.72	-40.15	111.21	0.00	0.00	0.00
2,600.00	3.00	338.84	2.596.99	108.60	-42.04	116.45	0.00	0.00	0.00
2,700.00	3.00	338.84	2,696.85	113.48	-43.93	121.68	0.00	0.00	0.00
2,800.00	3.00	338.84	2,796.71	118.36	-45.82	126.92	0.00	0.00	0.00
2,900.00	3.00	338.84	2,896.57	123.24	-47.70	132.15	0.00	0.00	0.00
2,949.49	3.00	338.84	2,946.00	125.65	-48.64	134.74	0.00	0.00	0.00
8 5/8"									
3,000.00	3.00	338.84	2,996.44	128.12	-49.59	137.38	0.00	0.00	0.00
3,100.00	3.00	338.84	3,096.30	133.00	-51.48	142.62	0.00	0.00	0.00
3,177.64	3.00	338.84	3,173.84	136.79	-52.95	146.68	0.00	0.00	0.00
Start Drop - 3.200.00	1.75 3.00	338.84	3,196.16	137.88	-53.37	147.85	0.00	0.00	0.00
3,200.00	3.00	338.84 338.84	3,196.16	137.88	-53.37 -55.26	153.08	0.00	0.00	0.00
3,349.07	3.00	338.84	3,345.03	145.16	-56.19	155.65	0.00	0.00	0.00
3,400.00	2 hold at 3349.07 3.00	338.84	3,395.89	147.64	-57.15	158.32	0.00	0.00	0.00
3,475.64	3.00	338.84	3,471.43	151.33	-58.58	162.28	0.00	0.00	0.00
3,500.00	2.57	338.84	3,495.76	152.44	-59.01	163.46	1.75	-1.75	0.00
3,600.00	0.82	338.84	3,595.71	155.20	-60.08	166.42	1.75	-1.75	0.00



SDIPlanning Report



Database: Company: EDM5000-RobertS-Local

US ROCKIES REGION PLANNING

 Project:
 UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-24A PAD

Well: NBU 921-24A1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-24A1BS

GL 4898 & KB 4 @ 4902.00ft (ASSUMED) GL 4898 & KB 4 @ 4902.00ft (ASSUMED)

True

Minimum Curvature

nned	Survey									
	Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
	3,647.07 4,962.29	0.00 0.00	0.00 0.00	3,642.78 4,958.00	155.52 155.52	-60.20 -60.20	166.76 166.76	1.75 0.00	-1.75 0.00	0.00 0.00
	WASATCH 7,667.29	0.00	0.00	7,663.00	155.52	-60.20	166.76	0.00	0.00	0.00
	MESAVERDE		0.00	7,000.00	100.02	-00.20	100.70	0.00	0.00	0.00
	9,862.29	0.00	0.00	9,858.00	155.52	-60.20	166.76	0.00	0.00	0.00
	SEGO									
	9,936.29	0.00	0.00	9,932.00	155.52	-60.20	166.76	0.00	0.00	0.00
	CASTLEGAT	E								
	10,352.29	0.00	0.00	10,348.00	155.52	-60.20	166.76	0.00	0.00	0.00
	BLACKHAW	K - BLACKHAW	K_NBU 921-24 <i>A</i>	A1BS						
	10,952.29	0.00	0.00	10,948.00	155.52	-60.20	166.76	0.00	0.00	0.00
	PBHL_NBU 9	921-24A1BS								

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BLACKHAWK_NBU 921 - plan hits target cent - Circle (radius 25.00)		0.00	10,348.00	155.52	-60.20	14,540,011.28	2,062,629.87	40° 1' 42.744 N	109° 29' 30.523 W
PBHL_NBU 921-24A1B\$ - plan hits target cent - Circle (radius 100.00		0.00	10,948.00	155.52	-60.20	14,540,011.28	2,062,629.87	40° 1' 42.744 N	109° 29' 30.523 W

Casing Points						
	Measured Depth	Vertical Depth		Casing Diameter	Hole Diameter	
	(ft)	(ft)	Name	(in)	(in)	
	2,949.49	2,946.00		8.625	11.000	

ormations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,659.73	1,658.00	GREEN RIVER				
	1,930.10	1,928.00	BIRDSNEST				
	2,498.88	2,496.00	MAHOGANY				
	4,962.29	4,958.00	WASATCH				
	7,667.29	7,663.00	MESAVERDE				
	9,862.29	9,858.00	SEGO				
	9,936.29	9,932.00	CASTLEGATE				
	10,352.29	10,348.00	BLACKHAWK				



SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-24A PAD

 Well:
 NBU 921-24A1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 921-24A1BS

GL 4898 & KB 4 @ 4902.00ft (ASSUMED) GL 4898 & KB 4 @ 4902.00ft (ASSUMED)

True

Minimum Curvature

Plan Annotations	Plan Annotations										
Measured	Vertical	Local Coor	dinates								
Depth	Depth	+N/-S	+E/-W								
(ft)	(ft)	(ft)	(ft)	Comment							
2.00	2.00	0.00	0.00	Start Build 2.00							
152.00	152.00	0.00	0.00	Start 3025.64 hold at 152.00 MD							
3,177.64	3,173.84	136.79	-52.95	Start Drop -1.75							
3,349.07	3,345.03	145.16	-56.19	Start 7603.22 hold at 3349.07 MD							
10,952.29	10,948.00	155.52	-60.20	TD at 10952.29							

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 1 of 14

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 921-24A Pad

<u>API #</u>		NBU 921-24A1BS						
	Surface:	239 FNL / 445 FEL	NENE	Lot				
	BHL:	83 FNL / 505 FEL	NENE	Lot				
<u>API #</u>								
	Surface:	240 FNL / 435 FEL	NENE	Lot				
	BHL:	413 FNL / 499 FEL	NENE	Lot				
<u>API #</u>	_	NBU 921-24A4BS						
	Surface:	241 FNL / 425 FEL	NENE	Lot				
	BHL:	743 FNL / 499 FEL	NENE	Lot				
<u>API #</u>	_	NBU 921-24A4CS	_					
	Surface:	242 FNL / 415 FEL	NENE	Lot				
	BHL:	1073 FNL / 498 FEL	NENE	Lot				

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on November 9, 2011. Present were:

- · David Gordon, Melissa Wardle BLM;
- · Bucky Secakuku BIA;
- · LeAllen Blackhair, Rainey Longhair Ute Indian Tribe;
- · Kelly Jo Jackson Montgomery Archeological Consultants Inc.;
- · Scott Carson Smiling Lake Consulting;
- · John Slaugh, Mitch Batty Timberline Engineering & Land Surveying, Inc.;
- Laura Abrams, Casey McKee, Raleen White, Doyle Holmes, Sheila Wopsock Kerr-McGee
- · Dan Hamilton Grasslands Consulting, Inc.
- · Justin Strauss SWCA Environmental Consultants

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with Onshore Order #1, Kerr-McGee will, in accordance with BMPs, improve or maintain existing roads in a condition

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 2 of 14

that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing will be performed where excessive rutting or erosion may occur. Dust control will be performed as necessary to ensure safe operating conditions.

Roads, gathering lines and electrical distribution lines will occupy common disturbance corridors where possible. Where available, roadways will be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor will overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Please refer to Topo B, for existing roads.

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BIA.

Each new well pad or pad expansion may require construction of a new access road and/or de-commissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, as per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met. As applicable, Kerr-McGee may use unimproved and/or two-track roads for lease operations, to lessen total disturbance.

Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities, such as V- or wing-ditches, will be constructed to divert surface water runoff. Drainage features, including culverts, will be constructed or installed prior to commencing other operations, including drilling or facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s), as necessary.

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activity will not be conducted using frozen or saturated materials or during periods when significant watershed damage

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 3 of 14

(e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating conditions. All vehicular traffic, personnel movement, construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

 $\pm 820^{\circ}$ (0.16 miles) – Section 24 (NE/4) and Section 13 (SE/4) T9S R21E – On lease UTU0149076 and UTU01193 Ute Indian Tribe surface, from the edge of the pad to the existing road in the SE/4 of Section 13 - 9S - 21E. Please refer to Topo B.

C. Location of Existing Wells:

A) Refer to Topo Map C.

D. Location of Existing and/or Proposed Facilities:

This is a new pad; therefore does not have any existing facilities. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore (Kerr-McGee).

Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad. A berm will be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will generally be constructed of compacted subsoil or corrugated metal, and will hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite (typically Shadow Gray). A production facility layout is provided as part of a project-specific APD, ROW or NOS submission.

GAS GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The gas gathering pipeline material: Steel line pipe. Surface = Bare pipe. Buried = Coated with fusion bonded epoxy coating (or equivalent). The total gas gathering pipeline distance from the meter to the tie in point is $\pm 2,285$ ' and the individual segments are broken up as follows:

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 4 of 14

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±2,285' (0.43 miles) – Section 24 T9S R21E (NE/4) – On-lease UTU0149076 Ute Indian Tribe surface, New 6" and 16" buried gas gathering pipeline from the meter to the NBU 921-24G intersection. Please refer to Topo D2 - Pad and Pipeline Detail.

LIQUID GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The total liquid gathering pipeline distance from the separator to the tie in point is $\pm 2,285$ ' and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±2,285' (0.43 miles) – Section 24 T9S R21E (NE/4) – On-lease UTU0149076 Ute Indian Tribe surface, New 6" buried liquid gathering pipeline from the meter to the NBU 921-24G intersection. Please refer to Topo D2 - Pad and Pipeline Detail.

Pipeline Gathering Construction

Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee. Gas gathering pipeline(s,) gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. The area of disturbance during construction from the edge of road or well pad will typically be 30' in width. Where pipelines run cross country, the width of disturbance will typically be 45 ft for buried lines and 30 ft for surface lines. In addition, Kerr-McGee requests for a permanent 30' disturbance width that will be maintained for the portion adjacent to the road. The need for the 30' permanent disturbance width is for maintenance and repairs. Cross country permanent disturbance width also are required to be 30ft.

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. In some surface pipeline installation instances pipe cannot be constructed where it will lay. In these cases where an above-ground pipeline is constructed parallel and adjacent to a road, it will be welded/fused on the road and then lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment.

Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2 inches (typically fuel gas lines) to 24 inches (typically transportation lines) in diameter, but 6 to 16 inches is typical for a buried gas line. The diameter of liquids pipelines may vary from 2 inches to 12 inches, but 6 inches is the typical diameter. Gas lift lines may vary from 2 to 12 inches in diameter, but 6-inch diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 5 of 14

Typically, to install a buried pipeline, topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6 feet, but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18-48 inches.

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route's intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, Kerr-McGee will apply all applicable Army Corps mandates as well as the BLM's Hydraulic Considerations for Pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface.

Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.

When no longer deemed necessary by the operator, Kerr-McGee or it's successor will consult with the Vernal BIA Office before terminating of the use of the pipeline(s).

The Anadarko Completions Transportation System (ACTS) information:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 6 of 14

allow for completion operations. The completion operations pit is lined and will be used for the wells drilled on the pad or used as part of our Anadarko Completions Transportation (ACTS) system which is discussed in more detail below. Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If Kerr-McGee does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit will be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The pit will be refurbished as follows when a traditional drill pit is used: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit.

All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit.

ACTS will require temporarily laying multiple 6" aluminum water transfer lines on the surface between either existing or refurbished reserve pits. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The temporary ACTS lines will be permitted under a separate cover to the Ute Indian Tribe.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. Kerr-McGee requests to keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. Kerr-McGee understands that due to the temporary nature of this system, BIA considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BIA.

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 7 of 14

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources:

Permit # 49-2307	JD Field Services	Green River- Section 15, T2N, R22E
Permit # 49-2321	R.N. Industries	White River- Section 2, T10S, R24E
Permit # 49-2319	R.N. Industries	White River- Various Sources
Permit # 49-2320	R.N. Industries	Green River- Section 33, T8S, R23E

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from Tribal lands without prior approval from the BIA. A source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BIA.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. Kerr-McGee also maintains a Spill Control and Countermeasure Plan, which includes notification requirements, including the BIA, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of CERCLA, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, Kerr-McGee will comply with the notification requirements of NTL-3A. Drill cuttings and/or drilling fluids will be contained in the reserve/frac pit whether a closed loop system is used or not. Cuttings will be buried in pit(s) upon closure. Unless specifically approved by the BIA, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc.). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by the BIA. Should timely removal not be feasible, the pit will be netted as soon as practical. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 8 of 14

The reserve and/or fracture stimulation pit will be lined with an impermeable liner. The liner will be a synthetic material 30 mil or thicker. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions (freeboard, etc.) allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per Onshore Order Number 7 (OSO 7). Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Otherwise, fluids disposal locations and associated haul routes, for ROW consideration, are typically depicted on Topo A of individual projects. Revisions to the water source or method of transportation will be subject to written approval from the BIA.

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 9 of 14

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. Kerr-McGee maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time. Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E NBU #159 in Sec. 35 T9S R21E Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 34 T9S R21E

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 10 of 14

H. Ancillary Facilities:

No additional ancillary facilities are planned for this location.

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits.

For the protection of livestock and wildlife, all open pits and cellars will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/ Produced Liquid tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BIA.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BIA for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 11 of 14

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by Kerr-McGee. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BIA will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site to the approximate contour that existed prior to pad construction, final grading will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers, where practical. The surface soil material will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep, where practical. The entire area will be uniformly covered with the depressions constructed perpendicular to the natural flow of water.

Reclamation of roads will be performed at the discretion of the BIA/Tribe. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications as proposed below in "Measures Common to Interim and Final Reclamation".

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BIA/Tribe.

Measures Common to Interim and Final Reclamation

Soil preparation will be conducted using a disk for areas in need of more soil preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

Seeding will occur year-round as conditions allow and will typically be accomplished through the use of a no-till rangeland style seed drill with a "picker box" in order to seed "fluffy" seed. Where drill seeding is not the preferred method, seed will be broadcast and then raked into the ground at double the rate of drill seeding. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-24A Pad Surface Use Plan of Operations 12 of 14

re-vegetation. The seed mixes will be selected from a list provided by or approved by the BIA/Tribe or a specific seed mix will be proposed by Kerr-McGee to the BIA/Tribe and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be maintained by Kerr-McGee. Every effort will be made to obtain "cheat grass free seed".

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Indian Ricegrass (Nezpar)	3
Sandberg Bluegrass	0.75
Bottlebrush Squirreltail	1
Great Basin Wildrye	0.5
Crested Wheatgrass	1.5
Winterfat	0.25
Shadscale	1.5
Four-wing Saltbrush	0.75
Forage Kochia	0.25
Total	9.5

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Weed Control

Noxious weeds will be controlled in akk orihect areas un accordance with all applicable rules and regulations.

K. Surface/Mineral Ownership:

Ute Indian Tribe

P.O. Box 70

Bureau of Land Management
988 South 7500 East Annex Building
Fort Duschesne, UT 84026

(435) 722-4307

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
(435)781-4400

L. Other Information:

Onsite Specifics:

Arch monitor during construction

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and Kerr-McGee will provide immediate notification to the BIA.

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 13 of 14

Resource Reports:

A Class I literature survey was completed on October 7, 2011 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 11-302.

A paleontological reconnaissance survey was completed on June 2, 2010 by SWCA Environmental Consultants. For additional details please refer to report UT11-14314-152.

Biological field survey was completed on October 10-11, 2011 by Grasslands Consulting, Inc (GCI). For additional details pleas refer to report GCI-603.

Proposed Action Annual Emissions Tables:

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	0.12	3.92
CO	2.2	0.11	2.31
VOC	0.1	4.9	5
SO_2	0.005	0.0043	0.0093
PM_{10}	1.7	0.11	1.81
PM _{2.5}	0.4	0.025	0.425
Benzene	2.2E-03	0.044	0.046
Toluene	1.6E-03	0.103	0.105
Ethylbenzene	3.4E-04	0.005	0.005
Xylene	1.1E-03	0.076	0.077
n-Hexane	1.7E-04	0.145	0.145
Formaldehyde	1.3E-02	8.64E-05	1.31E-02

 $[\]overline{\ }^1$ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	15.68	16,547	0.09%
VOC	20	127,495	0.02%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Uintah Basin Data

NBU 921-24A1BS/921-24A1CS/ 921-24A4BS/ 921-24A4CS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-24A Pad Surface Use Plan of Operations 14 of 14

M. Lessee's or Operators' Representative & Certification:

Laura Abrams Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6356 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Laura Abrams March 21, 2012
Date



Kerr-McGee Oil & Gas Onshore LP PO Box 173779 DENVER, CO 80217-3779

November 16, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 921-24A1BS

T9S-R21E

Section 24: NENE (Surface and Bottom Hole)

Surface: 239' FNL, 445' FEL Bottom Hole: 83' FNL, 505' FEL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling.

- Kerr-McGee's NBU 921-24A1BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing roads and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.


Therefore, based on the above stated information, Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joe Matney Sr. Staff Landman

Joe Matiney



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

June 4, 2012

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following well is planned for calendar year 2012 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

WELL PAD - NBU 922-24A

43-047-52768 NBU 921-24A1BS Sec 24 T09S R21E 0239 FNL 0445 FEL BHL Sec 24 T09S R21E 0083 FNL 0505 FEL

This office has no objection to permitting the well at this time.

Michael L. Coulthard

Digitally signed by Michael L Coulthard

Dibt cn=Michael L Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email-michael_Coulthard@blm.gov, c=US
Date: 2012.06.04 10:21:40-0600*


bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:6-4-12

RECEIVED: June 05, 2012




API Well Number: 43047 520 Jec 8 WTAB - UTM (feet), NAD27, Zone 12N


Site: NBU 921-24A PAD Well: NBU 921-24A1BS


Wellbore: OH

Design: PLAN #1 PRELIMINARY









CASTLEGATE

BLACKHAWK

750

TD at 10952.29

Vertical Section at 338.84° (1500 ft/in)

1500

BLACKHAWK_NBU 921-24A1BS

2250

8250

9000

9750

10500

11250


-750


SEGO

10948.00

Scientific Drilling

Rocky Mountain Operations





WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/29/2012 API NO. ASSIGNED: 43047527680000

WELL NAME: NBU 921-24A1BS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) PHONE NUMBER: 720 929-6356

CONTACT: Laura Abrams

PROPOSED LOCATION: NENE 24 090S 210E **Permit Tech Review:**

> SURFACE: 0239 FNL 0445 FEL **Engineering Review:**

> BOTTOM: 0083 FNL 0505 FEL Geology Review:

COUNTY: UINTAH

LATITUDE: 40.02805 LONGITUDE: -109.49214 **UTM SURF EASTINGS: 628661.00** NORTHINGS: 4431959.00

FIELD NAME: NATURAL BUTTES LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 0149076 PROPOSED PRODUCING FORMATION(S): BLACKHAWK

SURFACE OWNER: 2 - Indian **COALBED METHANE: NO**

RECEIVED AND/OR REVIEWED: LOCATION AND SITING: ✓ PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: FEDERAL - WYB000291

Potash R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

Oil Shale 190-13 **Drilling Unit**

Board Cause No: Cause 173-14 Water Permit: 43-8496

Effective Date: 12/2/1999 **RDCC Review:**

Siting: Suspends General Siting Fee Surface Agreement


✓ Intent to Commingle R649-3-11. Directional Drill

Commingling Approved

Comments: Presite Completed

Stipulations:

3 - Commingling - ddoucet 4 - Federal Approval - dmason 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 921-24A1BS API Well Number: 43047527680000 Lease Number: UTU 0149076

Surface Owner: INDIAN Approval Date: 8/22/2012

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the BLACKHAWK Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at http://oilgas.ogm.utah.gov

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
 - Requests to Change Plans (Form 9) due prior to implementation
 - Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
 - Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB No. 1004-0136 Expires July 31, 2010

5.	Lease Serial No.
٠,	UTU0149076

APPLICATION FOR PERMIT	TO DRILL OR REENTER	6. If Indian, Allottee or Tribe Nam	ie
la. Type of Work: 🛛 DRILL 🔲 REENTER		7. If Unit or CA Agreement, Name UTU63047A	
1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Otl	her Single Zone 🔀 Multiple Zone	8. Lease Name and Well No. NBU 921-24A1BS	
2. Name of Operator Contact: KERR-MCGEE OIL&GAS ONSHOREM LIPLaura.A	LAURA ARRAMS	9. API Well No. 43-047-52768	
3a. Address 1099 18TH STREET STE 600 DENVER, CO 80202	3b. Phone No. (include area code) Ph: 720-929-6356 Fx: 720-929-7356	10. Field and Pool, or Exploratory NATURAL BUTTES	
4. Location of Well (Report location clearly and in accorda	unce with any State requirements.*)	11. Sec., T., R., M., or Blk. and Sur	rvey or Area
At surface NENE 239FNL 445FEL 40	.028078 N Lat, 109.492284 W Lon ✓	Sec 24 T9S R21E Mer SLI	-
At proposed prod. zone NENE 83FNL 505FEL 40.0			
14. Distance in miles and direction from nearest town or post- APPROXIMATELY 40.5 MILES SOUTH OF VE	office* RNAL, UT	12. County or Parish UINTAH	13. State UT
 Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 	16. No. of Acres in Lease	17. Spacing Unit dedicated to this v	well
83'	640.00		
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. on file	
652'	10952 MD 10948 TVD	WYB000291	
21. Elevations (Show whether DF, KB, RT, GL, etc. 4898 GL	22. Approximate date work will start 10/01/2012	23. Estimated duration 30-60 DAYS	
	24. Attachments		
The following, completed in accordance with the requirements o	f Onshore Oil and Gas Order No. 1, shall be attached to t	his form:	
 Well plat certified by a registered surveyor. A Drilling Plan. A Surface Use Plan (if the location is on National Forest Systems Supplied to the Supplied of the Appropriate Forest Service Off 	em Lands, the 5. Operator certification	ns unless covered by an existing bond formation and/or plans as may be requi	·
25. Signature (Electronic Submission)	Name (Printed/Typed) LAURA ABRAMS Ph: 720-929-6356	Date 03/	/28/2012
Title REGULATORY ANALYST II			
Approved by (Signature)	Name (Printed/Typed) Jerry Kenczka	Date	
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	OCT	0 9 2012
Application approval does not warrant or certify the applicant hoperations thereon. Conditions of approval, if any, are attached.	CONDITIONS OF APPROVAL AT	TTACHED	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, n States any false, fictitious or fraudulent statements or representati	nake it a crime for any person knowingly and willfully to ons as to any matter within its jurisdiction.	make to any department or agency of	the United

Additional Operator Remarks (see next page)

Electronic Submission #134181 verified by the BLM Well Information System For KERR-MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal

NOTICE OF APPROVAL

OCT 19 2012

DIV. OFOIL CASCAGRING ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

1254511012 AG

NY 10/19/11



UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Well No:

API No:

Kerr-McGee Oil & Gas Onshore, LP

NBU 921-24A1BS

43-047-52768

Location: Lease No:

Agreement:

NENE, Sec. 24, T9S, R21E

UTU-0149076

Natural Buttes Unit

OFFICE NUMBER:

(435) 781-4400

OFFICE FAX NUMBER:

(435) 781-3420

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	_	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

Page 2 of 8 Well: NBU 921-24A1BS

8/28/2012

SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 designrated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop
 work and contact the Authorized Officer (AO). A determination will be made by the AO as to what
 mitigation may be necessary for the discovered paleontologic material before construction can
 continue.

Site-Specific Conditions of Approval:

- 1. Paint facilities "Shadow Gray."
- 2. Conduct a raptor survey prior to construction operations if such activities will take place during raptor nesting season (January 1 through September 30). If active raptor nests are identified during the survey, operations shall be conducted according to the seasonal restrictions detailed it the Uinta Basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah Raptor Guidelines.
- 3. If construction and /or drilling operations have not been initiated prior to October 10, 2012, conduct a biological survey to determine the presence of Uinta Basin hookless cactus in accordance with the guidelines specified in the USFWS Rare Plant Conservation measures and the BLM RMP ROD. KMG will implement commitments contained in the GNB BO.
- 4. Monitor construction operations with a permitted archaeologist.

ACTS Lines

- If construction and/or drilling operations have not been imitated prior to October 5, 2012, conduct a
 biological survey to determine the presence of Uinta Basin hookless cactus in accordance with the
 guidelines specified in the USFWS Rate Plant Conservation Measures and the BLM RMP ROD.
 KMG will implement commitments contained in the GNB BO.
- 2. Monitor areas with a permitted paleontologist where ACTS lines will travel through: Section 24-NWNW and NESE.
- 3. Fence site 42UN1025 prior to installation.

BIA Standard Conditions of Approval:

- 1. Soil erosion will be mitigated by reseeding all disturbed areas.
- 2. The gathering pipelines will be constructed to lie on the surface, unless otherwise specified. The surface pipelines will not be bladed or cleared of vegetation. Where pipelines are constructed parallel to roads they may be welded on the road and then lifted from the road onto the right-of-way. Where pipelines do not parallel roads but cross-country between sites, they shall be welded in

Page 3 of 8 Well: NBU 921-24A1BS

8/28/2012

place at well sites or on access roads and then pulled between stations with a suitable piece of equipment. Traffic will be restricted along these areas so that the pipeline right-of-way will not be used as an access road.

- 3. An open drilling system shall be used, unless otherwise specified, and included within the Application for Permit to Drill. The reserve pit shall be lined with a synthetic leak proof liner. After the drilling operation is complete, excess fluids shall be removed from the reserve pit and either hauled to an approved disposal site or shall be used to drill other wells. When the fluids are removed the pit shall be backfilled a minimum of 3.0 feet below the soil surface elevation.
- 4. A closed drilling system shall be used in all flood plain areas, and other highly sensitive areas, recommended by the Ute Tribe Technician, BIA, and other agencies involved.
- 5. A closed production system shall be used. This means all produced water and oil field fluid wastes shall be contained in leak proof tanks. These fluids shall be disposed of in either approved injection wells or disposal pits.
- 6. Major low water crossings will be armored with pit run material to protect them from erosion.
- 7. All personnel shall refrain from collecting any paleontological fossils and from disturbing any fossil resources in the area.
- 8. If fossils are exposed or identified during construction, all construction must cease and immediate notification to the Energy and Minerals Department and the Cultural Rights Protection Officer.
- 9. Before the site is abandoned the company will be required to restore the right-of-way to near its original state. The disturbed area will be reseeded with desirable perennial vegetation. If necessary, the Bureau of Indian Affairs or Bureau of Land Management will provide a suitable seed mixture.
- 10. Noxious weeds will be controlled on all surface disturbances within the project area. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.
- 11. If project construction operations are scheduled to occur during raptor nesting season (January 1 through September 30), KMG shall conduct raptor surveys in accordance with the guidelines specified in the Utah Field Office Guidelines for Raptor Protection from Human and Land Use disturbances, 2002. If active raptor nests are identified during a new survey, KMG shall conduct its operations according to the seasonal restrictions detailed in the Rod for the BLM Approved RMP and spatial offsets specified by the USFWS Utah Raptor Guidelines (See Appendix D).
- 12. USFWS threatened and endangered plant and animal conservation measures will be followed, as appropriate to the species identified by the biological resource survey and in conformation with the ROD of the BLM's Approved RMP (See Appendix D).
- 13. All personnel shall refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- 14. If artifacts or any culturally sensitive materials are exposed or identified during construction, all construction must cease and immediate notification to the Energy and Minerals Department and the Cultural Rights Protection Officer.

Page 4 of 8 Well: NBU 921-24A1BS

8/28/2012

15. Prior to commencing surveys or construction on the U&O Indian Reservation, the operator and any of its subcontractors shall acquire Access Permits and Business Licenses form the Ute Indian Tribe Energy and Minerals Department.

16. Prior to commencement of construction, the operator shall notify the Ute Indian Tribe Energy and Minerals Department of the date construction shall begin.

Page 5 of 8 Well: NBU 921-24A1BS

8/28/2012

DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

SITE SPECIFIC DOWNHOLE COAs:

- Gamma ray Log shall be run from Total Depth to Surface.
- Cement for the production casing must be brought 200' above the surface casing shoe.
- A CBL will be run from TD to TOC in the production casing.

Variances Granted:

Air Drilling

- 1. Properly lubricated and maintained rotating head. Variance granted to use a properly maintained and lubricated diverter bowl in place of a rotating head.
- 2. Blooie line discharge 100' from the well bore. Variance granted for blooie line discharge to be 45' from the well bore.
- 3. Compressors located in the opposite direction from the blooie line a minimum of 100' from the well bore. Variance granted for truck/trailer mounted air compressors located 40'from the well bore.
- 4. In lieu of mud products on location, Kerr McGee will fill the reserve pit with water for the kill medium and will utilize a skid pump near the reserve pit to supply the water to the well bore if necessary.
- 5. Automatic igniter. Variance granted for igniter due to there being no productive formations encountered while air drilling.
- 6. FIT Test. Variance granted due to well-known geology and the problems that can occur with the FIT test.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.

Page 6 of 8 Well: NBU 921-24A1BS

8/28/2012

 All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be reported in the driller's log.

- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is
 encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal
 Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM,
 Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 7 of 8 Well: NBU 921-24A1BS

8/28/2012

OPERATING REQUIREMENT REMINDERS:

 All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be
 notified when it is placed in a producing status. Such notification will be by written communication
 and must be received in this office by not later than the fifth business day following the date on
 which the well is placed on production. The notification shall provide, as a minimum, the following
 informational items:
 - o Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - o The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - o Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs,

Page 8 of 8 Well: NBU 921-24A1BS

8/28/2012

core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering
 lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a
 suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be
 obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover
 equipment shall be removed from a well to be placed in a suspended status without prior approval
 of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior
 approval of the BLM Vernal Field Office shall be obtained and notification given before resumption
 of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

Sundry Number: 40886 API Well Number: 43047527680000

	STATE OF UTAH		FORM 9
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 0149076	
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In	
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizon for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-24A1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047527680000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 80217	PHONE NUMBER: 73779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0239 FNL 0445 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 24 Township: 09.0S Range: 21.0E Merid	lian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICAT	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
7	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
8/22/2013	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION
Date of Work Completion.	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	✓ APD EXTENSION
Report Date:	WILDCAT WELL DETERMINATION	OTHER	OTHER:
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you. Date: August 07, 2013 By:			
NAME (PLEASE PRINT) Teena Paulo	PHONE NUMB 720 929-6236	ER TITLE Staff Regulatory Specialist	
SIGNATURE N/A		DATE 8/5/2013	

Sundry Number: 40886 API Well Number: 43047527680000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047527680000

API: 43047527680000 Well Name: NBU 921-24A1BS

Location: 0239 FNL 0445 FEL QTR NENE SEC 24 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/22/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

• If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
 Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
 Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
• Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? (Yes (No
• Has the approved source of water for drilling changed? Yes No
• Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
• Is bonding still in place, which covers this proposed well? Yes No
nature: Teena Paulo Date: 8/5/2013

Sig

Title: Staff Regulatory Specialist Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Sundry Number: 52654 API Well Number: 43047527680000

	STATE OF UTAH		FORM 9
DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 0149076	
SUNDRY NOTICES AND REPORTS ON WELLS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE	
	oposals to drill new wells, significantly or reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-24A1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047527680000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 80217	PHONE NUMBER: 3779 720 929-0	9. FIELD and POOL or WILDCAT: 6 INATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0239 FNL 0445 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 24 Township: 09.0S Range: 21.0E Meridi	an: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPOF	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
Kerr-McGee Oil & G an extension to this	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR WATER SHUTOFF WILDCAT WELL DETERMINATION COMPLETED OPERATIONS. Clearly show a cas Onshore, L.P. (Kerr-McGe APD for the maximum time a with any questions and/or co	e) respectfully requests allowed. Please contact	Approved by the
NAME (PLEASE PRINT) Teena Paulo	PHONE NUMBE 720 929-6236	R TITLE Staff Regulatory Specialist	
SIGNATURE N/A		DATE 6/26/2014	

Sundry Number: 52654 API Well Number: 43047527680000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047527680000

API: 43047527680000 Well Name: NBU 921-24A1BS

Location: 0239 FNL 0445 FEL QTR NENE SEC 24 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/22/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

• If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
 Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
 Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
• Has the approved source of water for drilling changed? Yes No
• Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
• Is bonding still in place, which covers this proposed well? 🌘 Yes 🔘 No
nature: Teena Paulo Date: 6/26/2014

Sig

Title: Staff Regulatory Specialist Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Form 3160-5 (August 2007)

HECEIVED

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

AUG 0 6 2014

FORM APPROVED OMB NO. 1004-0135

	Expires: July 31, 201
5.	Lease Serial No. UTU0149076

	OTICES AND REPORTS ON WELLS	
Do not use this	form for proposals to drill or to re-enter a D Use form 3160-3 (APD) for such proposa	N/
anangoneg well.	Use form 3160-3 (APD) for such proposa	IVI

6. If Indian, Allottee or Tribe Name

		-,		VI				
SUBMIT IN TRI	PLICATE - Other instruc	tions on reverse	side.		7. If Unit or 9 8910089	CA/Agreeme	ent, Name and/or	No.
1. Type of Well					8. Well Name NBU 921		<u>-</u>	
Oil Well Gas Well Ot				-				
2. Name of Operator KERR MCGEE OIL & GAS O	Contact: NSHORELMail: teena.paul	TEENA PAULO o@anadarko.com			9. API Well 43-047-5	No. 52768-00-2	X1	
3a. Address 1368 SOUTH 1200 EAST VERNAL, UT 84078	,	3b. Phone No. (incl Ph: 720-929-62 Fx: 720-929-723	36 É		10. Field and NATURA	Pool, or Ex AL BUTTE	ploratory S	
4. Location of Well (Footage, Sec., 7	., R., M., or Survey Description)			11. County o	r Parish, and	l State	
Sec 24 T9S R21E NENE 239 40.028078 N Lat, 109.492284					UINTAH	COUNTY	', UT	_
12. CHECK APP	ROPRIATE BOX(ES) TO	INDICATE NA	TURE OF N	OTICE, RE	EPORT, OR	OTHER I	DATA	
TYPE OF SUBMISSION			TYPE OF	ACTION				
■ Notice of Intent	☐ Acidize	Deepen		☐ Product	ion (Start/Res	ume) [□ Water Shut-	Off
- .	☐ Alter Casing	☐ Fracture 7	reat	☐ Reclama	ation	.[☐ Well Integrit	ty
☐ Subsequent Report	Casing Repair	☐ New Con	struction	☐ Recomp	lete		Other O	
☐ Final Abandonment Notice	☐ Change Plans	Plug and	Abandon	□ Tempor	arily Abandor		Change to Orig	inal A
	Convert to Injection	☐ Plug Back	ī	☐ Water D	Disposal			
following completion of the involved testing has been completed. Final Al determined that the site is ready for f Kerr-McGee Oil & Gas Onsho extension to this APD for the undersigned with any question APD: 10/9/12 NEPA: 2012-266-EA-3/17/12	bandonment Notices shall be fil- inal inspection.) ore, L.P. (Kerr-McGee) res maximum time allowed. P ns and/or comments. Tha	ed only after all require pectfully requests lease contact the	an O(ing reclamation CT 06 20 OIL, GAS	n, have been con	verne	the operator has	FICE
14. I hereby certify that the foregoing is	Electronic Submission #	E OIL & GAS O NSH	ORE L. sent	to the Verna		E)		
Name (Printed/Typed) TEENA F	PAULO	Title	STAFF	REGULATO	RY SPECIA	LIST		
Signatura (Electronic	Euhmission)	Date	00/0e/20	214				
Signature (Electronic					ee			
	THIS SPACE FO	A FEDERAL O						· · · · · · · · · · · · · · · · · · ·
Approved By	h	Titl			eld Manag oral Resour		SEP 04	2014
Conditions of approvaling any are attached certify that the applicant holds legal or equivalent would entitle the applicant to condition	d. Approval of this notice does uitable title to those rights in the act operations thereon.	not warrant or subject lease Off	ice V	ERNAL I	FIELD OF	PRCE		
Title 18 U.S.C. Section 1001 and Title 43	U.S.C. Section 1212, make it a	crime for any person k	nowingly and	willfully to ma	ake to any depar	rtment or age	ency of the United	d



Revisions to Operator-Submitted EC Data for Sundry Notice #256024

Operator Submitted

BLM Revised (AFMSS)

Sundry Type:

1,

OTHER NOI

UTU0149076

Agreement:

Lease:

UTU63047A

Operator:

KERR MCGEE OIL & GAS ONSHORE L 1368 SOUTH 1200 EAST VERNAL, UT 84078 Ph: 720-929-6236

Admin Contact:

TEENA PAULO STAFF REGULATORY SPECIALIST E-Mail: teena.paulo@anadarko.com

Ph: 720-929-6236 Fx: 720-929-7236

Tech Contact:

TEENA PAULO STAFF REGULATORY SPECIALIST E-Mail: teena.paulo@anadarko.com

Ph: 720-929-6236 Fx: 720-929-7236

Location:

State: County: UT UINTAH

Field/Pool:

NATURAL BUTTES

Well/Facility:

NBU 921-24A1BS Sec 24 T09S R21E Mer SLB NENE 239FNL 445FEL

APDCH NOI

UTU0149076

891008900A (UTU63047A)

KERR MCGEE OIL & GAS ONSHORE L 1368 SOUTH 1200 EAST VERNAL, UT 84078 Ph: 435.789.3995

TEENA PAULO STAFF REGULATORY SPECIALIST E-Mail: teena.paulo@anadarko.com

Ph: 720-929-6236 Fx: 720-929-7236

TEENA PAULO STAFF REGULATORY SPECIALIST E-Mail: teena.paulo@anadarko.com

Ph: 720-929-6236 Fx: 720-929-7236

UT UINTAH

NATURAL BUTTES

NBU 921-24A1BS Sec 24 T9S R21E NENE 239FNL 445FEL 40.028078 N Lat, 109.492284 W Lon

CONDITIONS OF APPROVAL

Kerr McGee Oil and Gas Onshore LP.

Notice of Intent APD Extension

Lease:

UTU-0149076

Well:

NBU 921-24A1BS

Location:

NENE Sec 24-T9S-R21E

An extension for the referenced APD is granted with the following conditions:

- The extension and APD shall expire on 10/09/2016. 1.
- 2. No other extension shall be granted.

If you have any other questions concerning this matter, please contact Robin L Hansen of this office at (435) 781-2777

Sundry Number: 64201 API Well Number: 43047527680000

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURG DIVISION OF OIL, GAS, AND MII		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 0149076
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizon for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-24A1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047527680000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 8021	PHONE NUMBER: 7 3779 720 929-	9. FIELD and POOL or WILDCAT: 1NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0239 FNL 0445 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 24 Township: 09.0S Range: 21.0E Merio	dian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
7	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
6/24/2015	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion.	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	✓ APD EXTENSION
Report Date:	WILDCAT WELL DETERMINATION	OTHER	OTHER:
Kerr-McGee Oil & G an extension to this	COMPLETED OPERATIONS. Clearly show Gas Onshore, L.P. (Kerr-McGAPD for the maximum time with any questions and/or c	ee) respectfully requests allowed. Please contact	Approved by the
NAME (PLEASE PRINT)	PHONE NUME	BER TITLE	
Jennifer Thomas	720 929-6808	Regulatory Specialist	
SIGNATURE N/A		DATE 6/24/2015	

Sundry Number: 64201 API Well Number: 43047527680000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047527680000

API: 43047527680000 Well Name: NBU 921-24A1BS

Location: 0239 FNL 0445 FEL QTR NENE SEC 24 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/22/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

• If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No
 Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No
• Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No
• Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No
• Has the approved source of water for drilling changed? Yes No
 Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No
• Is bonding still in place, which covers this proposed well? Yes No
nature: Jennifer Thomas Date: 6/24/2015

Sig

Title: Regulatory Specialist Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Sundry Number: 72562 API Well Number: 43047527680000

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 0149076
SUNDF	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizo n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-24A1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047527680000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 8021	PHONE NUMBER: 7 3779 720 929-	9. FIELD and POOL or WILDCAT: 6.4%ATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0239 FNL 0445 FEL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 24 Township: 09.0S Range: 21.0E Merio	dian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
7	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start: 6/24/2016	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
0/24/2010	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion.	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	✓ APD EXTENSION
Report Date:	WILDCAT WELL DETERMINATION	OTHER	OTHER:
Kerr-McGee Oil & G an extension to this	completed operations. Clearly show Gas Onshore, L.P. (Kerr-McGas Onshore, L.P.) (Kerr-McGas Onshore) and time with any questions and/or c	ee) respectfully requests allowed. Please contact	Approved by the
NAME (PLEASE PRINT) Joel Malefyt	PHONE NUMB 720 929-6828	BER TITLE Regualtory Analyst	
SIGNATURE N/A		DATE 6/24/2016	

Sundry Number: 72562 API Well Number: 43047527680000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047527680000

API: 43047527680000 Well Name: NBU 921-24A1BS

Location: 0239 FNL 0445 FEL QTR NENE SEC 24 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 8/22/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application. which should be verified.

owing is	a checklist of some	titems related to the application, which should be verified.	
• If location Yes		has the ownership changed, if so, has the surface agreement been upon	dated? 🔵
		ed in the vicinity of the proposed well which would affect the spacing ation? Yes No	or siting
	here been any unit o osed well?	or other agreements put in place that could affect the permitting or ope	eration of thi
	there been any chan osed location?	nges to the access route including ownership, or rightof- way, which co	ould affect th
• Has t	he approved source	of water for drilling changed? 🔵 Yes 📵 No	
		sical changes to the surface location or access route which will require ussed at the onsite evaluation? 🔘 Yes 📵 No	a change in
• Is bo	nding still in place, w	vhich covers this proposed well? 🌘 Yes 🔘 No	
	Joel Malefyt	Date : 6/24/2016	
		LEDD MOOFE OIL & OAG ONGLIODE L.D.	

Sig

Title: Regualtory Analyst Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT Green River District Vernal Field Office

170 South 500 East Vernal, UT 84078

 $\underline{http://www.blm.gov/ut/st/en/fo/vernal.html}$



NOV 1 0 2016

IN REPLY REFER TO: 3160 (UTG011)

Kerr McGee Oil & Gas LP Att: Joel Malefyt PO Box 173779 Denver, Colorado 80202-3779 RECEIVED

NOV 2 5 2016

DIV. OF OIL, GAS & MINING

Dear Joel Malefyt,

The referenced Applications for Permit to Drill (APD) have expired. According to our records, no known activity has transpired at the approved pads location. In view of the foregoing, this office is notifying you that the approval of the referenced applications has expired. If you intend to drill at these locations in the future, a new Application for Permit to Drill must be submitted.

43-047-

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
52815	UTU-0149076	NBU 921-24E4CS	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52838	UTU-0149076	NBU 921-24L1BS	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52836	UTU-0149076	NBU 921-24E4BS	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
	UTU-0149076	NBU 921-24E1CS	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
	UTU-0149076	NBU 921-24D	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
5 28 33	UTU-0149076	NBU 92124E1BS	SWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
5281b	UTU-0149076	NBU 921-24D4CS	NWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52823	UTU-0149076	NBU 921-24D4BS	NWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52812	UTU-0149076	NBU 921-24D1BS	NWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52814	UTU-0149076	NBU 921-24D1CS	NWNW	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
52800	UTU-0149076	NBU 921-24A4CS	NENE	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
52768	UTU-0149076	NBU 92124A1BS	NENE	Sec.24-T9S-R21E	4/9/2012	10/9/2012	10/9/2016
52801	UTU-0149076	NBU 921-24A1CS	NENE	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/5/2016
52799	UTU-0149076	NBU 921-24A4BS	NENE	Sec.24-T9S-R21E	4/9/2012	10/5/2012	10/15/2016

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
5282	7 UTU-0149076	NBU 921-24H4CS	SENE	Sec.24-T9S-R21E	4/9/2012	10/16/2012	10/16/2016
2828	UTU-0149076	NBU 92124H4BS	SENE	Sec.24-T9S-R21E	4/9/2012	10/16/2012	10/16/2016
1830	UTU-0149076 UTU-0149076	NBU 921-24H1BS	SENE	Sec.24-T9S-R21E	4/9/2012	10/16/2012	10/16/2016
	UTU-0149076	NBU 921-24H1CS	SENE	Sec.24-T9S-R21E	4/9/2012	10/16/2012	10/16/2016

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
52811	UTU-0149076	NBU 921-24C1CS	NENW	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
2810	UTU-0149076	NBU 92124C4BS	NENW	Sec.24-T9S-R21E	4/9/2012	10/9/2012	10/9/2016
	UTU-0149076	NBU 921-24F1BS	NENW	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
_		NBU 921-24C4CS	NENW	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
2809	UTU-0149076	NBU 921-24C1BS	NENW	Sec.24-T9S-R21E	4/9/2012	10/9/2012	10/19/2016

	Lease	Well	Aliquot	Sec., T., R.	Date Rec'd	APD Approved	Date Exp'd
52807	UTU-0149076	NBU 921-24B4CS	NWNE	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
	UTU-0149076	NBU 92124B1BS	NWNE	Sec.24-T9S-R21E	4/9/2012	10/9/2012	10/9/2016
52804	UTU-0149076	NBU 921-24B1CS	NWNE	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016
-	UTU-0149076	NBU 921-24B4BS	NWNE	Sec.24-T9S-R21E	4/9/2012	10/12/2012	10/12/2016

This office requires a letter confirming that no surface disturbance has been made for these drill sites. Any surface disturbance associated with the approved location of these wells is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

If you have any questions regarding this matter, please contact Beth Hamann at (435) 781-3430.

Sincerely,

gerrý Kenczka

Assistant Field Manager
Lands & Mineral Resources